

STORMWATER SYSTEM IMPROVEMENTS PHASE 1B

City of West Miami, Florida



CLIENT City of West Miami Public Works Dept.
901 SW 62nd Avenue
Miami, FL 33144
Contract # 4600000549

Contact: Juan Pena
Director Public Works
Tel (305) 266-4214
cwmjpena@bellsouth.net



PROJECT DESCRIPTION

To improve stormwater drainage and flood protection by providing an upgraded drainage and treatment system while maximizing water quality treatment of storm runoff as per NPDES requirements. Specifically, the City is to complete construction of a telemetry system, drainage pump stations 1 and 2, maintenance buildings and Phase III French drains.

SERVICES PERFORMED

Construction of the City of West Miami's stormwater collection and treatment system, including installation of a gravity collection system consisting of 12,278 LF of 15" to 60" drainage pipe, 2,400 LF of French Drain and construction of over 175 drainage structures. Additional work performed also included installation of 10,047 LF of 48" DIP stormwater Force Main, as well as, all other incidentals as indicated by the drawings and specifications or as required to properly complete the project as planned.

COMPLETION DATE

2006

PROJECT COST

\$ 5,832,493